

EnerTech Environmental, Inc.

Converting Biosolids to a Usable Fuel: The Emerging Technology of Biosolids Carbonization – The Rialto Regional Biosolids Facility

SCAP Workshop - Perris, California

September 28, 2004




Today's Agenda

- SlurryCarb[™] Process Overview
- Current SlurryCarb[™] Facilities
- Performance of the SlurryCarb[™] Process
- Utilization of E-Fuel
- The Rialto Regional Facility
- Advantages for the Region



The SlurryCarb™ Process







Current SlurryCarb Facilities

Rendering of Regional Facility Plant

Process Development Unit (PDU)



Process Performance


Viscosity of biosolids – 30% biosolids pumpable

- Reaction time less than 12 minutes
- Reacted product dewatered to greater than 50% solids
- Produced 6,500 Btu/lb E-Fuel using digested biosolids
- Pellet form preferred by market at 90% dry
- Combustion characteristics similar to coal and an excellent feedstock for the cement industry
- No residual remains at the end of the process



SlurryCarb Mass & Energy Balance

Assume 100 wet tons per day @ 20% solids



Utilization of E-Fuel

- The final product (a renewable fuel) reduces the volume of 20% biosolids by 84%
- Product fuel has ~6,500 Btu/lb (as pellet) and has economic value of lignite coal
- Fuel can be utilized in multiple scenarios:
 - cement kiln
 - gasifier
 - pulverized coal boiler
 - fluid bed
 - waste boiler other boilers
 - incinerator
 - in the process heater for internal energy needs








The California Regional Project

125 DTPD of Biosolids from the Region:

Biosolids Production _____ from Region


Current Stakeholders Include three municipalities




~110 tons E-Fuel

Environmental, \$ Inc.


Renewable E-Fuel to Cement Kiln











Project Location

I - 10 **Railroad Yard Riverside** Ave. **Tank Farm** Calif. Portland Cement Santa Ana Ave. **Holiday Rock Rialto WWTP Regional Facility** Yeager Landfill Aqua Mansa Rd **Duck Farms** Santa Ana River



California Project Status

- Finding Stakeholders biosolids commitments
- EIR in progress; air permit done (pending EIR)
- Fuel Users Located back-up is included
- Partners Secured
- Financing Structure (CPCFA and equity)
- Engineering has begun
- Begin operations in 2nd 3rd Q 2006





California Project Economics

- 1) Long-term, predictable cost
- 2) Avoided capital cost for digesters, dewatering, and/or dryers
- 3) Reduced chemical costs
- 4) Reduced operating costs
- 5) Reclaim land utilized for disposal issues
- 6) Reduced trucking costs with regional facility
- 7) Reduced energy costs

